

Questions & Answers
Oconto County Highway Department – Suring South
Shop

Comm Number: 54174-9801-96
BRRTS Number: 03-43-000563

Q1) A 5-ft. diameter x 10-ft. deep concrete manhole exists at the site. This manhole was used for active site remediation. I presume that the equipment should be removed from this manhole and it should be filled with soil or other suitable material. The concrete manhole top and the casting could either remain in place or could be removed. You may wish to address this issue so the bidders have a consistent understanding of how bids should be prepared. Refer to Record Drawing #5 in Appendix F of the Construction Documentation Report dated November 1994.

A1) The remediation system should be abandoned, dismantled, and removed upon conditional closure of the site per NR 726. All vertical elements of the system must be properly abandoned per requirements of NR 141.

Q2) The Record Drawings also refer to a 4-inch diameter groundwater discharge pipe to the on-site ditch. You may wish to have this pipe plugged or somehow abandoned.

A2) The remediation system should be abandoned, dismantled, and removed upon conditional closure of the site per NR 726. All vertical elements of the system must be properly abandoned per requirements of NR 141.

Q3) You may also wish to note that the extraction wells should be abandoned. Record Drawing #6 shows a typical extraction well cross-section.

A3) The remediation system should be abandoned, dismantled, and removed upon conditional closure of the site per NR 726. All vertical elements of the system must be properly abandoned per requirements of NR 141.